



## GM Chime Interface 2012-2016

### INTERFACE FEATURES

- Provides accessory power (12-volt 10-amp)
- Retains R.A.P. (Retained Accessory Power)
- Provides wires for multimedia radios (park brake, reverse, speed sense)
- Used in non-amplified models, or when bypassing a factory amplifier
- Used in models without OnStar<sup>®</sup> or when not retaining OnStar<sup>®</sup>
- Retains all warning chimes
- High level speaker input
- Retains balance and fade
- Micro “B” USB updatable

### INTERFACE COMPONENTS

- AXDI-GM44 interface
- LD-LCGM-044 harness

### TABLE OF CONTENTS

Applications .....	2
Connections LD-LCGM-044.....	3
Installation .....	4
Programming.....	4

### TOOLS & INSTALLATION ACCESSORIES REQUIRED

- Cutting tool
- Tape
- Crimping tool
- Connectors (i.e. butt-connectors, bell caps, etc.)

Visit [AxxessInterfaces.com](http://AxxessInterfaces.com) for more detailed information about the product and up-to-date vehicle specific applications

**ATTENTION:** With the key out of the ignition, disconnect the negative battery terminal before installing this product. Ensure that all installation connections, especially the air bag indicator lights, are plugged in before reconnecting the battery or cycling the ignition to test this product. **NOTE:** Refer also to the instructions included with the aftermarket accessory before installing this device.

## APPLICATIONS

### CHEVROLET

Avalanche † *	2012-2013
Express †	2013-2015
Malibu (with monochrome display)	2013-2015
Malibu Limited (with monochrome display)	2016-2016
Silverado 2500 / 3500 † *	2014

### CHEVROLET (CONT)

Silverado † *	2012-2013
Suburban † **	2012-2014
Tahoe † **	2012-2014
Trax	2015-2016

### GMC


Savana †	2013-2015
Sierra 2500 / 3500 † *	2014
Sierra † *	2012-2013
Yukon / Yukon XL † **	2012-2014

\* These vehicles have a digital amp option. Please reference the "Service Parts Identification" sticker located in the glove box for the RPO code Y91. If Y91 is present, then the vehicle is equipped with a digital amplifier.

\*\* These vehicles have a digital amp option. Please reference the "Service Parts Identification" sticker located in the glove box for the RPO codes; Y91, STZ, UQS. If Y91, STZ or UQS is present, then the vehicle is equipped with a digital amplifier.

† Only for models with NAV.

## CONNECTIONS: LD-LCGM-044 DIAGRAM



## INSTALLATION

### With the key in the off position:

- Connect the **LD-LCGM-044** harness into the interface, and then to the wiring harness in the vehicle.

## PROGRAMMING

**Attention!** If the interface loses power for any reason, the following steps will need to be performed again. Also, if installing an AXSWC connect it after you initialize and test the interface/radio, with the key in the off position.

- Turn the key (or push-to-start button) to the ignition position and wait until the radio comes on.

**Note:** If the radio does not come on within 60 seconds, turn the key to the off position, disconnect the interface, check all connections, reconnect the interface, and then try again.

- Turn the key to the off position, and then to the accessory position. Test all functions of the installation for proper operation, before reassembling the dash.

Having difficulties? We're here to help.



Contact our Tech Support line at:

**386-257-1187**



Or via email at:

[techsupport@metra-autosound.com](mailto:techsupport@metra-autosound.com)

### Tech Support Hours (Eastern Standard Time)

Monday - Friday: 9:00 AM - 7:00 PM

Saturday: 10:00 AM - 5:00 PM

Sunday: 10:00 AM - 4:00 PM



### **KNOWLEDGE IS POWER**

Enhance your installation and fabrication skills by enrolling in the most recognized and respected mobile electronics school in our industry. Log onto [www.installerinstitute.edu](http://www.installerinstitute.edu) or call 386-672-5771 for more information and take steps toward a better tomorrow.



**Metra recommends MECP  
certified technicians**